

2006 Data Summary Report

June 2007



Grasse River Study Area
Massena, New York



ALCOA

Alcoa Inc.
Massena, New York

TABLE OF CONTENTS

SECTION 1 INTRODUCTION.....	1-1
SECTION 2 2006 SRS PROGRAM	2-1
2.1 ROUTINE WATER COLUMN MONITORING	2-1
2.1.1 Monitoring Activities.....	2-1
2.1.2 Summary of Results.....	2-2
2.1.2.1 River Flow and Precipitation	2-3
2.1.2.2 Water Quality.....	2-3
2.1.2.3 PCBs	2-4
2.1.2.4 Comparison to Historic Data	2-5
2.2 RESIDENT FISH TREND MONITORING SURVEY	2-6
2.2.1 Monitoring Activities.....	2-6
2.2.2 Summary of Results.....	2-7
2.2.2.1 PCB Results	2-7
2.2.2.2 Comparison to Historic Data	2-9
2.3 TSS MONITORING DURING SPRING HIGH FLOW/ICE BREAKUP	2-10
2.3.1 Monitoring Activities.....	2-10
2.3.2 Summary of Results.....	2-11
2.3.2.1 Stage Height and Flow Data	2-11
2.3.2.2 Monitoring Results.....	2-12
2.3.2.3 Comparison to Historic Data	2-12
2.4 FIELD RECONNAISSANCE OF FISH ADVISORY SIGNS.....	2-13
2.4.1 Monitoring Activities.....	2-13
2.4.2 Summary of Results.....	2-13
SECTION 3 2006 POST-ROPS MONITORING.....	3-1
3.1 SEDIMENT SAMPLING	3-1
3.1.1 Monitoring Activities.....	3-1
3.1.2 Summary of Results.....	3-2
3.2 MULTIBEAM BATHYMETRY SURVEY	3-7
3.2.1 Monitoring Activities.....	3-7
3.2.2 Summary of Results.....	3-7
3.3 CAP OBSERVATION/UNDERWATER VIDEO	3-8
3.3.1 Monitoring Activities.....	3-8
3.3.2 Summary of Results.....	3-8
3.4 ECOLOGICAL MONITORING.....	3-9
3.4.1 Near Shore Benthic Community Characterization	3-10
3.4.1.1 Monitoring Activities.....	3-10
3.4.1.2 Summary of Results.....	3-10
3.4.2 Near Shore Aquatic Habitat Characterization.....	3-16
3.4.2.1 Monitoring Activities.....	3-16
3.4.2.2 Summary of Results.....	3-17
3.4.3 Summary of Ecological Monitoring Results.....	3-20

SECTION 4 2006 PHASE 1 SEDIMENT SAMPLING PROGRAM	4-1
4.1 MONITORING ACTIVITIES	4-1
4.2 SUMMARY OF RESULTS	4-3
SECTION 5 2006-2007 RIVER ICE MONITORING.....	5-1
5.1 CLIMATOLOGICAL CONDITIONS	5-2
5.2 RIVER STAGE MONITORING	5-3
5.2.1 River Stage During Ice Formation.....	5-3
5.2.2 River Stage During Ice Breaking and Natural Ice Breakup.....	5-6
5.3 MONITORING OF RIVER ICE FORMATION	5-7
5.4 ICE THICKNESS MEASUREMENTS AND SIMULATION	5-7
5.4.1 Ice Thickness Measurements	5-8
5.4.2 Ice Thickness Simulations	5-9
5.5 MONITORING OF RIVER ICE BREAKUP	5-12
5.5.1 Field Observations During Lower Grasse River Ice Breaking Demonstration Project	5-12
5.5.2 Field Observations Before and During Natural Ice Breakup.....	5-13
5.6 SUMMARY AND CONCLUSIONS.....	5-16
SECTION 6 QUALITY ASSURANCE/QUALITY CONTROL	6-1
6.1 INTRODUCTION.....	6-1
6.2 QA/QC PROCEDURES.....	6-1
6.3 RESULTS OF QA/QC ANALYSES	6-4
6.3.1 Water Column.....	6-4
6.3.2 Resident Fish.....	6-6
6.3.3 Sediment	6-7
6.3.3.1 PCBs (Aroclor).....	6-7
6.3.3.2 Total Organic Carbon	6-9
6.3.3.3 Grain Size.....	6-10
6.3.4 Invertebrate Community	6-11
6.4 SUMMARY	6-12
SECTION 7 REFERENCES.....	7-1

List of Tables

Table 1-1.	2006 Data Collection Summary.
Table 2-1.	Summary of 2006 SRS Monitoring Activities.
Table 2-2.	2006 SRS Water Column Monitoring Activities - PCB Results.
Table 2-3.	2006 SRS Water Column Monitoring Activities – Total Suspended Solids Results.
Table 2-4.	2006 Resident Fish Trend Monitoring - Number of Samples Collected/Number of Samples Targeted.
Table 2-5.	2006 Resident Fish Trend Monitoring Study - Adult Resident Fish Collection Field and Laboratory Data - Smallmouth Bass and Brown Bullhead.
Table 2-6.	2006 Resident Fish Trend Monitoring Study - Resident Fish Collection Field and Laboratory Data - Young-of-Year Spottail Shiner.
Table 2-7.	TSS Data Collected During 2006 High Flow Sampling at the Main Street and Alcoa Bridges.
Table 3-1.	Remedial Options Pilot Study – Sediment Core Sampling Summary.
Table 3-2.	Summary of Post-ROPS Sediment Vibracore Samples Collected from 7/25/2006 to 8/3/2006 from Work Zones 1, 2, Northern Near Shore, and Southern Near Shore.
Table 3-3.	Remedial Options Pilot Study – Comparison of Pre- and Post-Construction Data: Mean Percent Benthic Abundance.
Table 3-4.	Remedial Options Pilot Study – Comparison of Pre- and Post-Construction Data: Mean Benthic Metrics.
Table 3-5.	Remedial Options Pilot Study – Comparison of Pre- and Post-Construction Data: Mean Grain Size and TOC Results.
Table 3-6.	Remedial Options Pilot Study – Comparison of Pre- and Post-Construction Data: Mean Water Quality Measurements.

Table 3-7.	Remedial Options Pilot Study – Comparison of Pre- and Post-Construction Data: Summary of Aquatic Vegetation and Percent Abundance.
Table 4-1.	Summary of Phase 1 Vibracore Sediment Sampling.
Table 4-2.	Summary of Phase 1 Sediment Vibracore Samples Collected from 5/2-5/11/06 from the Main Channel and Side Slope Areas.
Table 4-3.	Average Sediment Depth and Volume Estimates of PCB Containing Sediments in the 2006 Phase 1 Fine Sediment Areas.
Table 5-1.	Ice Monitoring Locations.
Table 5-2.	Summary of Tape-Down Measurements.
Table 5-3.	Ice Thickness Measurements.
Table 6-1.	Individual Samples Not Meeting QA/QC Guidelines.

List of Figures

Figure 1-1.	Grasse River Study Area – Location Map.
Figure 2-1.	2006 SRS Program – Water Column Monitoring Locations.
Figure 2-2.	Grasse River Flow and Precipitation Information from 2006.
Figure 2-3a.	Water Temperature and Specific Conductivity Measurements During the 2006 SRS Program. (WCMSB to WC131)
Figure 2-3b.	Water Temperature and Specific Conductivity Measurements During the 2006 SRS Program. (WC011 to WC013)
Figure 2-4a.	Spatial Distribution of TSS Concentrations Measured During the 2006 SRS Program. (Rounds 1 to 8)
Figure 2-4b.	Spatial Distribution of TSS Concentrations Measured During the 2006 SRS Program. (Rounds 9 to 15)

- Figure 2-5. Monthly Average PCB Concentrations at Water Column Sampling Locations in 2006.
- Figure 2-6. Monthly Average PCB Mass Fluxes at Water Column Sampling Locations in 2006.
- Figure 2-7a. Spatial Distribution of Total PCBs in Water Samples Collected During the 2006 SRS Program. (Rounds 1 to 8)
- Figure 2-7b. Spatial Distribution of Total PCBs in Water Samples Collected During the 2006 SRS Program. (Rounds 9 to 15)
- Figure 2-8. Average Homolog Distributions in Water Samples Collected in 2006.
- Figure 2-9a. Seasonal Average Water Column PCB Concentrations Measured During Non-Stratified Periods. (WC007 and WC007A/WC131)
- Figure 2-9b. Seasonal Average Water Column PCB Concentrations Measured During Non-Stratified Periods. (WC011 and WC012)
- Figure 2-10a. Seasonal Average Water Column PCB Mass Fluxes Measured During Non-Stratified Periods. (WC007 and WC007A/WC131)
- Figure 2-10b. Seasonal Average Water Column PCB Mass Fluxes Measured During Non-Stratified Periods. (WC011 and WC012)
- Figure 2-11. 2006 SRS Program – Adult Smallmouth Bass Sample Collection Locations.
- Figure 2-12. 2006 SRS Program – Adult Brown Bullhead Sample Collection Locations.
- Figure 2-13. 2006 SRS Program – Young-of-Year Spottail Shiner Sample Collection Locations.
- Figure 2-14. Average Aroclor-Based PCB Concentrations in Fish Collected in Fall 2006.
- Figure 2-15. Average Aroclor-Based PCB Levels in Smallmouth Bass (1991-2006).
- Figure 2-16. Average Aroclor-Based PCB Levels in Smallmouth Bass from the Power Canal.
- Figure 2-17. Average Aroclor-Based PCB Levels in Brown Bullhead (1991-2006).
- Figure 2-18. Average Aroclor-Based PCB Levels in Young-of-Year Spottail Shiner (1998-2006).
- Figure 2-19. Water Column Sampling Locations in March 2006 (TSS Sampling).

- Figure 2-20. Stage Height, Flow, and Total Suspended Solids From March 28 - 30, 2006.
- Figure 2-21. Water Column TSS Concentrations Versus Stage Height. (March 28 - 30, 2006)
- Figure 2-22. Solids Concentrations Measured at the Main Street Bridge as a Function of River Flow.
- Figure 2-23. 2006 SRS Program – Fishing Advisory Sign Locations.
- Figure 3-1. 2006 Post-ROPS Monitoring – Sediment Core Collection Locations.
- Figure 3-2a. Vertical Distribution of PCBs in Post-Capping Sediment Cores from the Main Channel Area (Work Zone 1).
- Figure 3-2b. Vertical Distribution of PCBs in Post-Capping Sediment Cores from the Main Channel Area (Work Zone 1).
- Figure 3-3. Physical and Chemical Example of Material Settled on the Cap Surface.
- Figure 3-4. Vertical Distribution of PCBs in Post-Capping Sediment Cores from the Main Channel Area (Work Zone 2).
- Figure 3-5. Vertical Distribution of PCBs in Post-Capping Sediment Cores Collected from the Northern and Southern Near Shore Areas.
- Figure 3-6. Post-ROPS Sediment Elevation in the Main Channel Area based on Multibeam Bathymetry Data (Nov. 2005 and Aug. 06).
- Figure 3-7. Sediment Elevation Difference in the Main Channel Area based on Multibeam Bathymetry Data (Aug. 06 - Nov. 05).
- Figure 3-8. Post-ROPS Sediment Elevation in the Armored Cap Area based on Multibeam Bathymetry Data (Oct. 2005 and Aug. 06).
- Figure 3-9. Sediment Elevation Difference in the Armored Cap Area based on Multibeam Bathymetry Data (Aug. 06 - Oct. 05).
- Figure 3-10. Near Shore Dredging/Capping Invertebrate Community and Aquatic Habitat Monitoring Locations.
- Figure 4-1. Phase 1 Sediment Sampling Locations from May 2006.

- Figure 4-2. Physical Characteristics of Underlying Sediments from the Main Channel and Side Slopes (T8-T15).
- Figure 4-3. Physical Characteristics of Underlying Sediments Collected During ROPS and Phase 1 Activities.
- Figure 4-4a. Transects T8 to T9.5: Cross-Sections of River Bottom Elevation and Sediment Metrics Measured During the 2006 Phase I Vibracore Program.
- Figure 4-4b. Transects T10 to T11.5: Cross-Sections of River Bottom Elevation and Sediment Metrics Measured During the 2006 Phase I Vibracore Program.
- Figure 4-4c. Transects T12 to T13.5: Cross-Sections of River Bottom Elevation and Sediment Metrics Measured During the 2006 Phase I Vibracore Program.
- Figure 4-4d. Transects T14 to T15: Cross-Sections of River Bottom Elevation and Sediment Metrics Measured During the 2006 Phase I Vibracore Program.
- Figure 4-5. 2006 Phase 1 Probing, Penetration, and Recovery Depths in the Main Channel and Side Slope (T8-T15).
- Figure 4-6. 2006 Phase 1 Probing Depths and DoC Estimates in the Main Channel and Side Slope (T8-T15).
- Figure 5-1. 2006/2007 Grasse River Ice Monitoring Locations.
- Figure 5-2. Typical Water Surface Elevation of the Grasse River.
- Figure 5-3. Air Temperature for Winter 2006/2007, Massena, NY.
- Figure 5-4. Precipitation Data and Stage Height for Winter 2006/2007, Massena, NY.
- Figure 5-5. Grasse River Stage Height and Flow for Winter 2006/2007, Chase Mills, New York USGS Gaging Station.
- Figure 5-6. Grasse River Stage Height for Winter 2006/2007, Alcoa Outfall 001 Staff Gage, Massena, NY.
- Figure 5-7. Stage Height and Flow for the Spring 2007 Ice Breakup, Chase Mills USGS Staff Gage and Outfall 001 Staff Gage.
- Figure 5-8. Lower Grasse River Ice Thickness Forecasting Model, Simulated Results and 15-Day Forecast, January 29, 2007.
- Figure 5-9. Lower Grasse River Ice Thickness Forecasting Model, Simulated Results through February 27, 2007.

- Figure 5-10. Lower Grasse River Ice Thickness Forecasting Model, Simulated Results Through Natural Breakup.
- Figure 5-11. Lower Grasse River Progression of Natural Ice Breakup, March 27 – 29, 2007.
- Figure 5-12. Lower Grasse River Photographs During 2006/2007 Natural Ice Breakup.

Appendices

- Appendix A. Grasse River Geographic Information Systems (GIS) Project Database.
- Appendix B. Post-ROPS Sediment Core Photos/Profiles.
- Appendix C. Post-ROPS OSI Bathymetry.
- Appendix D. Post-ROPS Underwater Video Cap Observations.
- Appendix E. Phase 1 Vibracore Sediment Core Photos/Profiles.
- Appendix F. Spring 2007 Ice Monitoring Photos.
- Appendix G. Spring 2007 Ice Breakup Video Observations.